# Document made available under the Patent Cooperation Treaty (PCT)

International application number: PCT/IL05/000304

International filing date: 17 March 2005 (17.03.2005)

Document type: Certified copy of priority document

Document details: Country/Office: US

Number: 60/570,535

Filing date: 13 May 2004 (13.05.2004)

Date of receipt at the International Bureau: 06 June 2005 (06.06.2005)

Remark: Priority document submitted or transmitted to the International Bureau in

compliance with Rule 17.1(a) or (b)



25 MAY 2005

<u>TO ALL TO WHOM THESE; PRESENTS; SHALL COME;</u>;

UNITED STATES DEPARTMENT OF COMMERCE

**United States Patent and Trademark Office** 

**April 29, 2005** 

THIS IS TO CERTIFY THAT ANNEXED HERETO IS A TRUE COPY FROM THE RECORDS OF THE UNITED STATES PATENT AND TRADEMARK OFFICE OF THOSE PAPERS OF THE BELOW IDENTIFIED PATENT APPLICATION THAT MET THE REQUIREMENTS TO BE GRANTED A FILING DATE UNDER 35 USC 111.

APPLICATION NUMBER: 60/570,535

FILING DATE: *May 13, 2004* 

By Authority of the

COMMISSIONER OF PATENTS AND TRADEMARKS

T. LAWRENCE

**Certifying Officer** 

PTO/SB/16 (01-04)

Approved for use through 07/31/2006. OMB 0651-0032

U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Vander the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

PROVISIONAL APPLICATION FOR PATENT COVER SHEET

This is a request for filing a PROVISIONAL APPLICATION FOR PATENT under 37 CFR 1.53(c).

Express Mail Label No.

		thi graying	061					<b>-</b>
Given Name (first and mir	ddo (if amil)	INVENTO		<del></del>		lesidence		
Given Name (first and middle [if any])		Family Name or Surname		(City	(City and either State or Foreign Coun			_i
ELAN		211	MD	RA	MAT G	FAV	ISRAEL	_
Additional inventors are b	eing named on the		_separately numb	bered sheet	s attached h	ereto		_
TITLE OF THE INVENTION (500 characters max)								
MULTI DIMENSIONAL FLEXIBLE MIDHRETURAL SUPPORT DEUCE FOR PREVENTION								
Direct all correspondence	to: CORR	ESPONDENCE ADDRESS	of	- URIM	are in	CONTIN	FACE IN	1
Customer Number:				FE	MALE	2	. <b>5</b> 7	
OR						<del></del>	9,0	
Firm or Individual Name	ELAN	211 MD	)				7,	
Address	0 1	DILANOT	37				15	3
Address	<del>- 8</del> -	TAILT I					- 29	케를
City		-0.6 0.0 d	State		Zip		11.0	
		MAT GAN	Telephone	<u> </u>	Fax _L		648	_
Country	SRF	المسترا		<u> </u>		9+2-3-	-7369263	듸
	ENCLO	SED APPLICATION PA	ARTS (check all	that appl	מ			-1
Specification Numb	ar of Pages	<b>8</b> .		CD(s), Numi	ber			1
	·	7						1
Drawing(s) Number	r of Sheets		ٔ لیا ،	Other (speci	Ty)			1
Application Data St	neet. See 37 CFR 1.7	6						
METHOD OF PAYMENT	OF FILING FEES FO	OR THIS PROVISIONAL A	PPLICATION FOR	PATENT				<b>-</b>
Applicant claims er	mail entity status. Sec	37 CFR 1.27.				G FEE		
A check or money	order is enclosed to o	cover the filing fees.			Amou	mt (\$)	7	
	by authorized to char				#	80		1
fees or credit any o	overpayment to Depo	sit Account Number:			**	<i>y</i> 0	1	ĺ
Payment by credit	card. Form PTO-203	8 is attached.			<u> </u>		<u></u>	
The invention was made United States Government		United States Government	or under a contrac	t with an ag	ency of the			
	54 11.		•					i
No.								1
Yes, the name of the	ne U.S. Government a	gency and the Governmer	t contract number	are:				1.
		[Page 1	of 21					
Respectfully submitted,	,	·ge ·		Date	3	0.4.0	4	
SIGNATURE	_ <b>/</b> K	ď	F	REGISTRAT	ION NO.			
(if appropriate)								
I TPED OF PRINTED NA				Docket Num	oer			
TELEPHONE		52-356992		··· cop 64				
This collection of information	n is required by 37 CFR	FOR FILING A PROVISIO 1.51. The information is required	red to obtain or retain	a benefit by	the public wh	ich is to file (a	and by the USPT	0
to process) an application.	Confidentiality is govern	led by 35 U.S.C. 122 and 37	CFR 1.14. This coll	ection is estin	nated to take	8 hours to c	complete, includin	ng .
gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and								
Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450, DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO: Mail Stop Provisional Application, Commissioner for Palents, P.O. Box 1450, Alexandria, VA 22313-1450.								
If you need assistance in completing the form, call 1-800-PTO-9199 and select option 2.								
		mo 414	theotollowin	ıg I				
	. The F	TO did not receive	eck 1	~ I	BEST	AMAIR	ABLE (	دسا <i>ک</i>
	listed	7-0-1	4	_	_ <u></u> _ 1	# TA TO # TANK		ノジン
		\$ 80,00		- :				

_	
O:	
=	•
8	•
=	,

to the above-identified deposit account.

DAGIC EIL ING EEE

FEE CALCULATION

SUBTOTAL (2)

Dr Elan Ziv MD

or number previously paid, if greater, For

SUBMITTED BY

Name (Print/Type)

Signature

PTO/SB/17 (10-03)
Approved for use through 07/31/2006. OMB 0851-0032
U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1895, no persons are required to respond to a collection of information unless it displays a valid QMB control number. Complete if Known FEE TRANSMITTAL **Application Number** MARKSHMEN2004 May 2004 11 Filing Date for FY 2004 Dr Elan Ziv First Named Inventor Effective 10/01/2003. Patent fees are subject to annual revision. **Examiner Name** Applicant claims small entity status. See 37 CFR 1.27 Art Unit (\$) 80 Attorney Docket No. TOTAL AMOUNT OF PAYMENT FEE CALCULATION (continued) METHOD OF PAYMENT (check all that apply) 3. ADDITIONAL FEES Money Order Check Credit card erge Entity , Small Entity Deposit Account: Fee . Code Fee Description Fee Pald Code (2) Deposit 130 2051 65 Surcharge - tate filing fee or oath 1051 25 Surcharge - late provisional filing fee or cover sheet Number 1052 2052 50 Deposit Account 130 Non-English specification Name 1053 130 1053 Director is authorized to: (check all that apply) 1812 2,520 For filing a request for ex parte reexamination 1812 2,520 Credit any overpayments Charge fee(s) indicated below 920\* Requesting publication of SIR prior to Examiner action 1804 920 1804 Charge any additional fee(s) or any underpayment of fee(s) 1805 1,840\* Requesting publication of SIR after Examiner action Charge fee(s) indicated below, except for the filing fee

1805 1.8401

110

420

2251

2252

1251

1252

1. DASIC I		-	<b>L</b>	1253	950 N	2253	475	Extension for reply within tritio month	
Large Entity Fee Fee	Small Entity Fee Fee	Fee Description	Fee Pald		1,480	2254	740	Extension for reply within fourth month	
Code (\$)	Code (\$)			1255	2.010	2255	1.005	Extension for reply within fifth month	
1001 770	2001 385	Utility filing fee			•				
1002 340	2002 170	Design filing fee		1401	330	2401		Notice of Appeal	
1003 530	2003 265	Plant filing fee		1402	330	2402		Filing a brief in support of an appeal	
1004 770	2004 385	Reissue filing fee		1403	290	2403		Request for oral hearing	l
1005 160	2005 80	Provisional filing f	ee 80	1451	1,510	1451	1,510	Petition to institute a public use proceeding	
1003 100	200	SUBTOTAL (1)		1452	110	2452	55	Pelition to revive - unavoidable	
	<u> </u>			1453	1,330	2453	665	Petition to revive - unintentional	
2. EXTRA	CLAIM FE	ES FOR UTILITY	AND REISSUE	1501	1,330	2501	665	Utility issue fee (or reissue)	
			below Fee Paid	1502	460	2502	240	Design issue fee	
Total Claims		20** = X	:=	1503	640	2503	320	Plant issue fee	
Independent Claims		-3"= X		1460	130	1460	130	Petitions to the Commissioner	
Multiple Dep	endent			1807	50	1807	50	Processing fee under 37 CFR 1.17(q)	
1 ama Entity	1 Small En	Hhu		1806	180	1806	180	Submission of Information Disclosure Stmt	
Fee Fee	Fee Fe		on		•			Recording each patent assignment per	
Code (\$)	Code (\$	<del>-</del>		8021	40	8021	40	property (times number of properties)	<u></u>
1202 18	2202	9 Claims in excess	s of 20	1809	770	2809	385	Filing a submission after final rejection	Į.
1201 86	2201	43 Independent clai	ims in excess of 3	•		1		(37 ČFR 1.128(a))	}
1203 290	2203	145 Multiple depend	ent claim, if not paid	1810	770	2810	385	For each additional invention to be examined (37 CFR 1.129(b))	L
1204 86	2204	43 ** Reissue inder over original p		1801	770	2801	385		
1205 18	2205		is in excess of 20	1802	900	1802	900	Request for expedited examination	
10	1 2255	and over origin		1				of a design application	<del></del>
				Othe	r fee (s;	ecify) _			

WARNING: Information on this form may become public. Credit card information should not be included on this form. Provide credit card information and authorization on PTO-2038.

This collection of information is required by 37 CFR 1.17 and 1.27. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.14. This collection is estimated to take 12 minutes to complete, including gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRI SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.

"Reduced by Basic Filing Fee Paid

Registration No.

(Attornay/Agent).

If you need assistance in completing the form, call 1-800-PTO-9199 and select option 2.

(\$)

sues, see above

2

SUBTOTAL (3)

(Complete (if applicable))

Telephone +97237369261

(\$)

March 14, 2004

55 Extension for reply within first month

210 Extension for reply within second month

## MULTI-DIMENSIONAL FLEXIBLE MIDURETHRAL SUPPORT DEVICE FOR PREVENTION OF URINARY INCONTINENCE IN FEMALES

The present invention relates generally to the field of treatment of urinary incontinence in female patients. More specifically, the present invention relates to a disposable device for use in the treatment of urinary incontinence in women. The invention describes a vaginal disposable device which is inserted and removed in a no-self-touch technique, by the patient herself, using a disposable applicator.

Inventor: Dr Elan Ziv, MD OBGYN, Urogynecologist

### **Background of the Invention**

5

10

15

20

25

30

Urinary incontinence is a widespread problem among females. It is estimated that up to 50% of women occasionally leak urine involuntarily, and that approximately 25% of woman will seek medical advice at some point in order to deal with the problem. Stress incontinence, the most common type of urinary incontinence, refers to the involuntary loss of urine resulting from abdominal pressure rise, occurring during exercise, coughing, sneezing, laughing, etc. When stress incontinence occurs, it is usually the result of the abnormal descent of the urethra and bladder neck below the level of the pelvic floor. While many different factors may contribute to the development of stress incontinence, it is most prevalent among women ages 35-65 and those who have had multiple vaginal deliveries. Stress incontinence is both aggravating and unpleasant for women, and it can also be embarrassing. Many women wear sanitary pads or diapers in order to deal with incontinence, though this is not a real solution to the problem and it can be very inconvenient and unreliable. Surgical treatment may involve securing the paraurethal tissues to the periosteum of the pubic bone or the rectus facia in order to elevate the bladder neck above the pelvic floor and thereby distribute pressure equally to the bladder, the bladder neck, and the mid-urethra. Recently, a procedure known as "TVT" ("Tension Free Vaginal Tape") was developed, in which a mesh tape is implanted underneath midurethra, creating a hammock on which the urethra may kink during physical effort.

<sup>&</sup>quot;Multi-dimensional flexible midurethral support device for prevention of female urinary incontinence"

Dr Elan Ziv, MD OBGYN, Urogynecologist

Page 1 of 8

However, surgery is only suitable for severe cases, and the majority of women experiencing incontinence do not need surgical solutions.

One modality of non-surgical treatment involves the use of devices that are inserted into the vagina, either by a medical practitioner or by the woman herself. Most devices are designed to apply pressure against the bladder neck so as to inhibit or completely block the flow of urine through the urethra. A variety of such devices are known in the art. For example, refer to U.S. Patent No. 5,618,256 to Reimer, entitled, "Device for Arrangement in the Vagina for Prevention of Involuntary Urination with Females and an Applicator for use in Insertion of the Device;" U.S. Patent No. 5,785,640 to Kresch, entitled "Method for Treating Female Incontinence;" U.S. Patent No. 4,920,986 to Biswas, entitled, "Urinary Incontinence Device;" U.S. Patent 5,417,226 to Juma, entitled, "Female Anti-Incontinence Device;" U.S. Patent No. 5,386,836 to Biswas, entitled, "Urinary Incontinence Device;" and U.S. Patent No. 5,007,894 to Enhorning, entitled, "Female Incontinence Device."

15

25

30

10

5

The existing non-surgical incontinence devices suffer from numerous drawbacks:

- A number of devices are constructed so as to completely block the urethra and thus
  they need to be removed or collapsed in order to allow the woman to urinate, an
  inconvenience for the woman wearing the device.
- To overcome this drawback, vaginal devices have been developed having specialized shapes that do not completely block the bladder neck. These devices tend to be large, uncomfortable, and intrusive. They also tend to cause irritation or soreness to the vagina.
  - Such devices are expensive to manufacture, and therefore, they are designed to be reusable and/or to remain in the vagina for an extended period of time. Such devices
    are normally made from large bodies of resilient material, such as plastic or hard
    rubber, in order to preserve their functioning for the required amount of time.
  - Most devices known in the art also tend to be difficult or painful to insert and/or remove. In order to correctly inhibit urine flow, the device needs to be properly positioned in the vaginal canal. As stated previously, a doctor may be required to properly position the device.

<sup>&</sup>quot;Multi-dimensional flexible midurethral support device for prevention of female urinary incontinence"
Dr Elan Ziv, MD OBGYN, Urogynecologist Page 2 of 8

- In cases where a doctor has to insert the device, the device is adapted for remaining in
  the vagina for a prolonged period of time. When positioned in the vagina for an
  extended period of the time, the device may cause vaginal infections, necrosis, or
  bleeding.
- The device may block or inhibit the flow of normal body secretions through the vagina, and may cause inflammation of the vagina and a foul-smelling discharge.

10

15

In cases where the device is designed to be inserted by the woman herself, the device
often has to be removed, cleaned, and then re-inserted after a predetermined number
of hours.

All vaginal devices so far described or marketed have at least one of the limiting features described above. No vaginal device for controlling urinary incontinence has so far been successfully marketed and used by the woman herself. There is a need for a device for controlling involuntary urination that is disposable, easy and comfortable for a woman to use, that works effectively and reliably, and that is completely sanitary and hygienic.

<sup>&</sup>quot;Multi-dimensional flexible midurethral support device for prevention of female urinary incontinence"

Dr Elan Ziv, MD OBGYN, Urogynecologist

Page 3 of 8

#### The Invention

The present invention provides a device for the treatment of urinary incontinence females. The device of the present invention is adapted to be disposable, worn only for a maximum of 16 hours and then discarded and replaced with a new device (if needed).

- The device of the present invention is simple and easy to use, and is inserted effortlessly in the same user-friendly and familiar manner that a tampon is inserted into the vagina during menstruation. As opposed to large and intrusive devices of the prior art, the device of the present invention is comfortable, and, once inserted, the woman need not think about it again until it is removed.
- When involuntary urination occurs, it is usually the result of the abnormal descent of the bladder neck and the urethra into a low position, away from the intra-abdominal pressure system. This "hypermobility" is the result of some injury to the support mechanism which normally keeps the urethra and the bladder neck in a raised position, along the backside of the pubic bone. The lowering of the bladder neck and the urethra that occur, for example, when a woman coughs, sneezes, or laughs, causing involuntary leakage of urine. The device of the present invention is designed so as to provide a "cradle" or shelf-like support to the urethra whenever the urethra descends momentarily, so as to prevent the leakage of urine. The device does not put pressure against the urethra or the bladder neck, but only provides support when there is a rise in abdominal pressure.

20

25

30

5

10

15

The present invention relates to a disposable device for the prevention of involuntary urination in females, adapted for being inserted into the vagina, comprising;

- (a) an internal support structure
- (b) a cover covering said internal support structure and comprised of a flexible material, and;
- (c) an applicator coupled to the internal support structure and the cover for facilitating insertion of the device into the vagina;

The main device and the cover are adapted for forming a cradle support for the midurethra following insertion of the device into the vagina so as to prevent involuntary urination while allowing for voluntary urination.

<sup>&</sup>quot;Multi-dimensional flexible midurethral support device for prevention of female urinary incontinence"

Dr Elan Ziv, MD OBGYN, Urogynecologist

Page 4 of 8

The invention will now be described with reference to accompanying drawings:

- FIG. 1A is a side view of the internal support structure.
- FIG. 1B is a top view of the internal support structure
- FIG. 1C is a perspective view of the internal support structure
- FIG. 2A is a side view of the extender.
- FIG. 2B is a top view of the extender
- FIG. 2C is a perspective view of the extender
- FIG. 3A is a sectional side view of the internal support structure at rest
- FIG. 3B is a sectional side view of the extended internal support structure
- FIG. 4A is a perspective view of the covering
  - FIG. 4B is a perspective view of the main device inside the covering.
  - FIG. 5 is a perspective view of the applicator.
  - FIG. 6 is a sectional view of the invention within the applicator
  - FIG.7 is a side view of the female pelvis.

The core of the device is a one prolonged embodiment (FIG 1A) which has three distinct parts:

- 1. A top section (8) which serves as the "anchoring" element, for stabilizing the device within the vagina,
- A bottom section (10) which serves as the "supporting" element, generating midurethral support,
  - 3. An intermediate section (9) which connects top & bottom elements. Along its longitudinal axis, there is a central tunnel (11) which allows for the passage of the extending insert.
- Each element of the device (FIG 1A+B+C) has 4 flexible arms. These arms of the anchoring element (8), force the device to remain in situ within the vagina, unable to move inwards or outwards, or to rotate. This occurs as a result of the special tendency of vaginal walls to collapse and form an occluded lumen. The flexible arms of the device cause "tenting" of the walls on top of them with resultant sagging of the walls around the intermediate section, thereby stabilizing the device. The arms of the supporting element

5

10

15

20

<sup>&</sup>quot;Multi-dimensional flexible midurethral support device for prevention of female urinary incontinence"

Dr Elan Ziv, MD OBGYN, Urogynecologist

Page 5 of 8

(10) cause elevation of the tissues around mid-urethra, acting as a hammock. This hammock supports mid-urethra in a tension free manner, much like the TVT operation.

The support element has between its arms an extender (FIG 2A+B+C) which is a separate unit. This extender has two distinct parts: the tucker (14) with its enlarged arrow head (15), arising from the flat bottom plate (12). This flat plate is made of flexible material (such as silicone, polyurethane, etc) which enables easy folding into the applicator. The tucker is forcefully pushed into the central tunnel, thereby allowing for its anchoring to the device.

5

10

15

20

25

30

In its resting position (FIG 3A), the extender does not influence expansion of the arms. The plate is within the space between the arms, without changing dimensions of the support element. FIG 3B shows the same device after forward pushing of the extender. The plate is now much closer to the intermediate section of the device, thereby forcefully spreading the arms, enlarging the diameter of the supporting element. This is essential for creating a device with changing dimensions for treating patients with various vaginal sizes.

The plate has another distinct feature, besides changing diameters. It also serves as a support element for the arms, mainly when a larger diameter is needed, to negate the forces from the vaginal walls.

The tucker may be pushed in to different depths along the central canal, thereby allowing for a wide range of diameters of the support element. The wider arrow head ensures a secured placement due to its wider diameter.

The device and the extending unit will be assembled together and introduced into the cover (FIG 4).

The cover (FIG 4A) is made of a flexible smooth mesh material (17) designed as small sack with a string (18). FIG 4B shows the device (20) within the tightly closed mesh cover (22). The cover allows for:

- Reduction of the friction between vagina and the device during insertion & removal.
- Reduction of the friction between the applicator and the device during insertion.
- Pulling the string causes straightening of the cover, straightening of the vaginal walls, allowing for an easy and smooth removal of the device from the vagina.

<sup>&</sup>quot;Multi-dimensional flexible midurethral support device for prevention of female urinary incontinence"

Dr Elan Ziv, MD OBGYN, Urogynecologist

Page 6 of 8

- Pulling the string causes the arms to fold slightly towards the midline, thereby reducing its size, allowing for an easy and smooth removal of the device from the vagina.
- The mesh of the cover, being stretched between the arms of the device, also serve as a
  hammock. In a woman who leaks urine during a stressful event (when abdominal
  pressure rises during coughing, sneezing, etc.), the urethra sags down but meets the
  hammock in its mid part. That also causes an elevation of the intra urethral pressure
  with resultant urinary continence.
- The applicator serves for insertion of the device into the vagina (FIG 5), as is done when inserting a regular menstrual tampon. The device is kept within the wider part (26) that is inserted into the vagina. When pushing the plunger (28), the device is pushed through the flower like opening (24), allowing for its immediate action once the applicator is removed from the vagina. The string (32) is visible, protruding out of the opening of the plunger (30).

When the device is still within the applicator (FIG 6), its flexible arms (34) converge towards the midline, allowing for the small dimensions and its insertion via a small diameter applicator. After insertion (FIG 7), the flexible arms of the device gain their preintended tension, enlarge the diameter of the device (46) within the vagina (48), anchoring itself under the bladder (40) between the uterine cervix (36) and the pubic bone (38), supporting mid-urethra (42). The string protrudes out of the vaginal introitus (44), as with the regular menstrual tampon, allowing for removal.

25

20

5

30

<sup>&</sup>quot;Multi-dimensional flexible midurethral support device for prevention of female urinary incontinence"

Dr Elan Ziv, MD OBGYN, Urogynecologist

Page 7 of 8

The invention has in its basic concept the following features:

- Being a disposable device.
- Insertion of the device is always with an applicator.
- Easy & comfortable insertion and removal.
- Being comfortable to wear.

5

10

20

- Being hygiene & odorless
- Being a familiar procedure to most female patients as inserting a menstrual tampon.
- Being inserted by the patient herself, in a no-self-touch technique, with a disposable inserter.
- Being removed by the patient herself, in a no-self-touch technique, with the device collapsing and becoming of small size for painless removal.
- Being of high availability, easy to get everywhere, sold as an Over the Counter (OTC) device.
- Being of low cost.
  - Having complete confidentiality, as with the use of menstrual tampons.
  - Having the ability to be removed instantly when needed.
  - No blockage of vaginal discharge.
  - Wide range of diameters

#### Alternative embodiments of the invention.

- It may be manufactured in different sizes
- It may be made of many flexible materials, such as silicone, polyurethane, etc.
- It can have more or less than 4 arms.
  - The angle between the arms may be changed.
  - There might be different shapes and curves of the arms


"Multi-dimensional flexible midurethral support device for prevention of female urinary incontinence"


Dr Elan Ziv, MD OBGYN, Urogynecologist

Page 8 of 8


"Multidimensional flexible midurethral support device for prevention of female urinary incontinence" Dr Elan Ziv, MD OBGYN, Urogynecologist

"Multidimensional flexible midurethral support device for prevention of female urinary incontinence" Dr Elan Ziv, MD OBGYN, Urogynecologist






"Multidimensional flexible midurethral support device for prevention of female urinary incontinence" Dr Elan Ziv, MD OBGYN, Urogynecologist



"Multidimensional flexible midurethral support device for prevention of female urinary incontinence" Dr Elan Ziv, MD OBGYN, Urogynecologist

2/7

"Multidimensional flexible midurethral support device for prevention of female urinary incontinence" Dr Elan Ziv, MD OBGYN, Urogynecologist



"Multidimensional flexible midurethral support device for prevention of female urinary incontine. Dr Elan Ziv, MD OBGYN, Urogynecologist

1/1